



2369 Ocean Ave., Suite 200
San Francisco, CA 94127

P: 415.282.1602
F: 415.282.1603

License # 416130
EIN # 94-2775973

info@vintagecontractors.com
vintagecontractors.com

Napa: 707.253.1841
Monterey: 831.658.0225

Proposal and Contract

Created Date 8/27/2026

Quote Number 10930-v3
Estimator Danny Doan

Client

Contact Name Josh Berta

Quote To Name City of Santa Clara
Quote To 2600 Benton St
Santa Clara, CA 95050

Project

Project Name Steve Carli Park - Resurface basketball court
Project Address 1045 Los Padres Blvd
Santa Clara, CA 95050

Resurface Existing Basketball Court Approximately 3,000 SF

Clean and scrape surface	
Flood and fill areas of standing water: Straightedge leveling of low areas to eliminate standing water. Assumes the court has industry standard 1% slope and average of 3 water holes less than 10' diameter and 3/8" depth. Additional corrections will be additional cost.	
Lance and/or grind cracks	
Fill cracks with acrylic patch compound	
Repair deteriorated asphalt with Laykold Deep Patch	\$2,107.36
Apply one (1) coat of acrylic resurfacer	
ACRYLIC ATHLETIC SURFACING: Squeegee apply three (3) coats of Plexipave acrylic athletic surfacing over prepared substrate.	\$11,010.00
STRIPING: Paint basketball court lines for 1 basketball court(s) per existing layout Note - additional striping will be additional cost.	\$2,770.00
NOTES: ALL CRACKS WILL REAPPEAR IMMEDIATELY. Maintenance resurfacing only. Will follow contours of existing substrate. Assumes existing tennis court has 1% slope to drain all in one direction to within 1/8" +/- in 10' tolerance. Access for pick-up trucks directly to work area. Electricity and water to be provided at all times within 50' of work area.	
Resurface Existing Basketball Court TOTAL:	\$15,887.36

Alternate #1: Expand and Resurface
Existing Basketball Court

Court size to be standard high school basketball without safety zones: 84' x 50'
Approximately: 4,200 SF

Lance and/or grind cracks	
Clean and scrape surface	



2369 Ocean Ave., Suite 200
San Francisco, CA 94127

P: 415.282.1602
F: 415.282.1603

License # 416130
EIN # 94-2775973

info@vintagecontractors.com
vintagecontractors.com

Napa: 707.253.1841
Monterey: 831.658.0225

Flood and fill areas of standing water: Straightedge leveling of low areas to eliminate standing water. Assumes the court has industry standard 1% slope and average of 3 water holes less than 10' diameter and 3/8" depth. Additional corrections will be additional cost.	
Repair deteriorated asphalt with Laykold Deep Patch	\$4,214.73
Fill cracks with acrylic patch compound	
Apply one (1) coat of acrylic resurfacer	
ACRYLIC ATHLETIC SURFACING: Squeegee apply three (3) coats of Plexipave acrylic athletic surfacing over prepared substrate.	\$15,414.00
STRIPING: Paint basketball court lines for 1 basketball court(s) per layout provided by owner. Note - additional striping will be additional cost.	\$2,770.00
NOTES: ALL CRACKS WILL REAPPEAR IMMEDIATELY. Maintenance resurfacing only. Will follow contours of existing substrate. Assumes existing tennis court has 1% slope to drain all in one direction to within 1/8" +/- in 10' tolerance. Access for pick-up trucks directly to work area. Electricity and water to be provided at all times within 50' of work area.	
INSTALL: Two (2) Basketball Goals - Basketball goals to be furnished by the City - Adjustments to accommodate old footings may come at an additional cost. - New footing depth to be 50: deep and 20" wide. Adjustments may come at an additional cost if necessary. - Basketball goals shall be installed per manufacturer's instructions and guidelines using 5,000 PSI concrete. Note: Existing basketball goals to be demo, off-hauled and footings backfilled by the City.	\$6,978.83
Alternate #1: Expand and Resurface Existing Basketball Court TOTAL:	\$29,377.56

Proposal Notes

NOTES: Vintage is non-union paying prevailing wages. Payment terms to be 30 days upon completion. Retention will follow pay when paid clause but will not exceed 90 days after completion. Completion is defined as walk-through with owner and approval for usage/occupancy by the owner.	
PREVIOUS CRACK REPAIRS: If the existing court has a "fabric" topical crack repair system over the cracks, this can be removed and the crack can be filled and reappear after resurfacing, or the material can be left in place. Resurfacing will not prevent or repair the fabric from wrinkles, ripples, additional edge cracks, or dead spots. The contractor has no responsibility for existing cracks or fabric crack repair systems in place. If Slipsheet Overlay is chosen, fabric will be removed and cracks will not return, so this disclaimer would not apply.	
BY OTHERS: Root control/barrier and cutting. Tree/bush/limbs pruned away from court surface and overhanging and intertwined with fence. Root barriers and root removal/cutting outside court to prevent roots from growing into/under court.	
NOTE: If shop drawings, diagrams, logos or other amenities not included in the base contract are required, we can provide these at an additional cost. Please contact your estimator / project manager for further information.	



2369 Ocean Ave., Suite 200
San Francisco, CA 94127

P: 415.282.1602
F: 415.282.1603

License # 416130
EIN # 94-2775973

info@vintagecontractors.com
vintagecontractors.com

Napa: 707.253.1841
Monterey: 831.658.0225

COLD WEATHER NOTES:

Any surfacing and coating work performed between October and the end of May carries a risk of failure, and owners must accept responsibility for that risk.

- Air Temperature: The temperature must be efficient to evaporate the water.
- Surface Temperature: A cold surface (below 50 degrees F) will hinder the rate of water evaporation.
- Relative Humidity: Higher humidity will slow the rate of drying.
- Rain: Application is prohibited during rain or when rain is imminent.
- Sunlight/Shade: The sun can warm the surface to the proper temperatures. Absence of sun can affect the surface temperature by more than 10 degrees F.
- Air Movement: Air movement is needed to change the relative humidity at the surface/atmosphere contact point.
- Coating/Film Thickness: Thicker coatings will take significantly longer to dry.
- Surface Color: Darker surfaces dry more quickly.

Proposal Notes TOTAL:

\$0.00



2369 Ocean Ave., Suite 200
San Francisco, CA 94127

P: 415.282.1602
F: 415.282.1603

License # 416130
EIN # 94-2775973

info@vintagecontractors.com
vintagecontractors.com

Napa: 707.253.1841
Monterey: 831.658.0225

Proposal and Contract

Created Date 8/27/2026

Quote Number 10930-v3
Estimator Danny Doan

Client

Contact Name Josh Berta

Quote To Name City of Santa Clara
Quote To 2600 Benton St
Santa Clara, CA 95050

Project

Project Name Steve Carli Park - Resurface basketball court
Project Address 1045 Los Padres Blvd
Santa Clara, CA 95050

Payment Terms: PROGRESS PAYMENTS. PAYMENT UPON COMPLETION OF EACH ITEM. RETENTION WILL FOLLOW "PAY WHEN PAID CLAUSE" BUT WILL NOT EXCEED 90 DAYS AFTER COMPLETION. COMPLETION IS DEFINED AS WALKTHROUGH WITH OWNER AND APPROVAL FOR USAGE/OCCUPANCY BY THE OWNER.

Signature

All material is guaranteed to be as specified. All work to be completed in a workmanlike manner according to standard practices. Any alteration or deviation from above specifications involving extra costs, will be executed only upon written orders, and will become an extra charge over and above the estimate. All agreements contingent upon strikes, accidents or delays beyond our control. Owner to carry fire, tornado and other necessary insurance.

Vintage Contractors is non-union paying prevailing wages.

Our workers are fully covered by Workmen's Compensation Insurance. Note: This proposal may be withdrawn by us if not accepted within 30 days. In the event legal action is instituted by either party hereto, the prevailing party shall be entitled to reasonable attorney's fees and costs.

Acceptance of Proposal

The above prices, specifications and conditions are satisfactory and are hereby accepted. You are authorized to do the work as specified. Payment will be made as outlined above.

Accepted:

Date: